CITY OF REDONDO BEACH

DEPARTMENT OF ENGINEERING AND BUILDING SERVICES

ADDENDUM

Date: November 21, 2012

To: All Bidders

From: City Engineer / Chief Building Official

Subject: **Addendum No. 2 – Veterans Park Community Center Condenser/ HVAC Replacement Project, Job No. 20500**

The following changes to the contract documents for the above subject project shall be incorporated into the plans and specifications of said project and made part thereof:

1. Contractor may upgrade the existing Johnson Control system to include new control requirement or provide new control system and connect existing Johnson Control system to new system. Contractor shall provide the City with new software and password for the control system. The City does not have the software and password of the existing system. All control and power wiring shall be in EMT conduit.

2. All outdoor supporting and anchoring devices shall be stainless steel..

3. On Drawing M-1, General Notes #12, the Equipment Performance Testing requirement is the same as the requirement as the Field Quality Control section in each Technical Specifications sections.

4. In Specifications, Technical Specifications, Section15761, at 2.1.I.3, Tube Diameter is specified as 0.25 inches. However, if Contractor's proposed coil manufacturer has different size but can perform the required coil performance as scheduled on Drawing M-1 is also acceptable.

5. The construction sign as shown in Exhibit N is not required for this project.

Acknowledgment of this Addendum shall be executed and attached to your Bid Proposal form. Failure to do so shall result in your bid being rejected.

CITY OF REDONDO BEACH

By: _____
Steve Huang, City Engineer/Chief Building Official

ACKNOWLEDGED

Bidder's Name: _____

Authorized Representative: _____ Date: _____