CITY OF REDONDO BEACH

DEPARTMENT OF ENGINEERING AND BUILDING SERVICES

ADDENDUM

Date: August 27, 2014

To: All Bidders

From: City Engineer

Subject: **Addendum No. 1 – Herondo Street/Harbor Drive Gateway Improvement Project Job No. 40900**

The following changes to the contract documents for the above subject project shall be incorporated into the plans and specifications of said project and made part thereof:

A. Section 1.11 of the General Conditions of the Specifications is hereby deleted in its entirety and replaced with the following:

1.11 Signs

Contractor shall post (4) – 3'x6' (shown on Exhibit H), weather-proof signs at key locations. Said sign locations shall be selected by staff and shall change as the location of the work area changes.

B. Section 7.2 of the Special Conditions of the Specifications is hereby deleted in its entirety and replaced with the following:

1.12 7.2 ASPHALT CONCRETE HOT- MIX

The Asphalt Concrete Hot-Mix shall be comprised of C2 and PG-64-10. When asphalt concrete is laid in two layers, it will include C2-PG-64-10 surface course over B-PG-64-10 base course. Colored C2-PG-64-10 shall be used as a surface course where indicated on the plans. Cycle Track area except at conflict points shall be green. Three (3) – 2'x2' mock up samples of the colored asphaltic concrete shall be submitted to the Engineer for approval. Asphalt color shall be Hot Mix Integral Color as manufactured by ChemSystems Incorporated, or approved equal, and shall be installed per manufacturer specifications.

C. The following note is added in its entirety to the General Construction Notes on Sheet T2 of the project plans:

14. Where the plans and or specification call for installation of new conduits, the material of the conduit shall be Schedule 80 PVC. All PVC Schedule 80 pipe shall be manufactured from a Type I, Grade I Polyvinyl Chloride (PVC) compound with a Cell Classification of 12454 per ASTM D1784. The pipe shall be manufactured in strict compliance to ASTM

D1785, consistently meeting and/or exceeding the Quality Assurance test requirements of this standard with regard to material, workmanship, burst pressure, flattening, and extrusion quality.

D. The following note is added in its entirety to the General Construction Notes on Sheet T2 of the project plans:

15. The Contractor shall maintain at ALL TIMES pedestrian, bike, vehicular access to the surrounding businesses and residences.

E. Section 2.3 of the Special Conditions of the Specifications is hereby deleted in its entirety and replaced with the following:

1.13 2.3 SPECIAL EVENTS

In an effort to facilitate the annual Redondo Beach Superbowl Sunday 10K/5K event on February 2, 2015, the Contractor shall schedule the project and coordinate with the event sponsors (including the City of Redondo Beach and Redondo Beach Chamber of Commerce) such as to ensure a safe and unobstructed event.

Acknowledgment of this Addendum shall be executed and attached to the Bid Proposal form. Failure to do so shall result in disqualifying the bid.

CITY OF REDONDO BEACH

By: Wisam Altowaiji
Wisam Altowaiji, City Engineer

ACKNOWLEDGED

Bidder's Name: _____

Authorized Representative: _____ Date: _____