



CITY OF REDONDO BEACH
PUBLIC WORKS DEPARTMENT
ENGINEERING SERVICES DIVISION

ADDENDUM NO. 1

Date: October 13, 2016
To: All Bidders
From: Acting City Engineer
Subject: **Addendum No. 1- Ensenada Parkette Improvements Project, Job No. 30620**

The following changes to the contract documents for the above subject project shall be incorporated into the plans and specifications of said project and made part thereof:

- 1. The bid opening date has been changed.** The sealed proposals for this project will be received at the office of the City Clerk of the City of Redondo Beach, 415 Diamond Street, Door C, Redondo Beach, California, **until 9:00 A.M., on October 24, 2016.**
2. Removal of grass to 2" deep and planting succulent plants shall be done by others. Contractor shall be responsible for the remaining of the landscaping work including but not limiting to soil preparation, grading, etc. Contractor shall coordinate with other work forces as required to complete the project construction.
3. Contractor is responsible for the traffic control plans complying with California Manual on Uniform Traffic Control Devices (CA-MUTCD) on street vehicular traffic control, sidewalk closing, etc. Contractor shall maintain street vehicular traffic open at all times. Sidewalk along the parkette may be closed during construction. The traffic control plans shall be reviewed and approved by the City Traffic Engineer. Traffic control plans may be prepared by Contractor.
4. Contractor is required to obtaining a no fees City Engineering permit for this project prior to start of construction.
5. The power of the electrical conduit, connecting the pump (transfer switch panel) and electrical pull box on site, running through the existing fence can be shut off between 10:00 A.M. and 3:00 P.M. for a period of 2 to 3 hours. The City will coordinate with the Contractor on the power shut off scheduling for the existing fence removal and new fence installation.
6. The Public Works Standards, Inc.'s Standard Plans for Public Works Construction (SPPWC) and Standard Specifications for Public Works Construction (SSPWC), latest edition, shall be part of the project specifications.

7. Contractor shall provide expansion joints per SPPWC Standard Plan 618-3 between existing and new retaining walls.
8. Concrete for retaining wall footings, other footings, and on-site ADA compliant accessible ramp shall be Class 560-C-3250 with 4" maximum slump. Concrete slab, walkway, sidewalk, etc. shall be Class 520-C-2500 with 4" maximum slump. City approved deputy inspectors and continuous inspections are required for pouring concrete more than 2,500 psi and placing structural steel for retaining walls and on-site ADA compliant accessible ramp
9. All metal welding shall be done by Los Angeles County certified welders and fabricating shops, or approved equal.
10. Drawings: Sheet 3, Detail C: The spacing for #5 horizontal rebars is 16" on center.
11. Drawings: Sheet 4 of 7 is replaced by attached **Sheet 4R**. Revisions on this sheet shall govern if there is any conflict with other sheets.
12. Drawings: Sheet 7, Detail F: The 3" perforated PVC pipe shall connect to existing catch basin to be relocated and replaced in kind along existing wall on Armour Lane. Said catch basin shall connect to existing piping system at the old location.
13. Drawings: Sheet 7, Key Note 26: Revise "1 ½" thick Vitriturf...or approved equal" to read "**3**" thick Vitriturf's rubberized play surfacing base **mat** or approved equal."
14. Specifications: Technical Specifications, Section 02880, Part 2, Paragraph 2.01 A. (Page 149): Revise "Shall be Mira-Therm Therapeutic... color: Forest Green" to read "Shall be Mira-Therm Therapeutic... color: **Royal Blue.**"
15. Specifications: Technical Specifications, Section 02880, Part 2, Paragraph 2.02 A. (Page 149): Revise "Shall be Mira-Therm 6' bench in-ground Model #1266, color: Forest Green" to read "Shall be Mira-Therm 6' **Portable Bench Model #1266-1**, color: **Royal Blue.**"
16. Specifications: Technical Specifications, Section 02880, Part 2, Paragraph 2.02 A. (Page 149): Revise "Shall be Mira-Therm Trash Receptacle Model #1129, color: Forest Green" to read "Shall be Mira-Therm **Litter Liminator Model #1129**, color: **Royal Blue.**"
17. Approved equal products: Contact: Nathan Younker, Playcore dba GameTime at (858)344-0445 or nate@gwppark.com
 - a. Tables: Ultra-Site's 8' Accessible Picnic Table Walk-through Design Model #238H-P8; Color: Blue.
 - b. Benches: Ultra-Site's 6' Portable Bench with Back Model #940P-P6; Color: Blue.
 - c. Trash Receptacles: Ultra-Site's 32 gallon Trash Receptacle Model #EX-32 with Lid RT-32 and Liner PL-32; Color: Blue.
 - d. Small Boulder: GameTime's Dome Boulder Model #38226.

- e. Climbing Wall with Ring: GameTime's Cosmix Climber Model #7064. Submit color and material samples for City's selection. Contractor shall provide 3.5" thick Vitriturf rubberized play surfacing base mat at no additional cost to the City if he/she chooses this product substitution instead of the specified.

Acknowledgment of this Addendum shall be executed and attached to your Bid Proposal form. Failure to do so shall result in your bid being rejected.

CITY OF REDONDO BEACH

By: Geraldine Trivedi
Geraldine Trivedi, Acting City Engineer

ACKNOWLEDGED

Bidder's Name: _____

Authorized Representative: _____ Date: _____